

19 Aprile 2024 *Piacenza - CIG* 

Spektra a Trimble Company

Tecnologia in campo: lastre in calcestruzzo 5.0



### I vantaggi della connected construction



#### **Connected construction can reduce:**



Engineering hours by 10-30%



Build costs by 5-10%



Operating costs by 10-20%



Decommissioning hours by 10-30%



## **Workflow Concrete Paving**



Rilievo



Analisi Dati



Costruzione - Machine control



Monitoraggio



Asset Management

Condivisione Cloud














#### Architettura del sistema



3 stazioni robotiche
Prisma attivo MT900
Radio on-machine
Slope Sensor GS420
Display Operatore CB430
Software Paving PCS900



#### Machine control con Guida semiautonoma





### Controllo in quota





### **Precisione data logging**





### Verifica e collaudo






### **WorksOS**





### WorksManager





### Report IRI

Start Station	End Station	Length (ft)	Average IRI ( in/mile)	Average Prl ( in/mile )	Road (Finish)	
					IRI ( in/mile )	Prl ( in/mile )
10+18.70	10+33.46	14.764	0.149	0.000	0.149	0.000
10+33.46	10+48.23	14.764	0.162	0.000	0.162	0.000
10+48.23	10+62.99	14.764	0.099	0.000	0.099	0.000
10+62.99	10+77.75	14.764	0.115	0.000	0.115	0.000
10+77.75	10+92.52	14.764	0.167	0.000	0.167	0.000
10+92.52	11+07.28	14.764	0.119	0.000	0.119	0.000
11+07.28	11+22.05	14.764	4.471	0.000	4.471	0.000
11+22.05	11+36.81	14.764	4.430	0.000	4.430	0.000
11+36.81	11+51.57	14.764	1.514	0.000	1.514	0.000
11+51.57	11+66.34	14.764	1.474	0.000	1.474	0.000
11+66.34	11+81.10	14.764	0.547	0.000	0.547	0.000
11+81.10	11+95.86	14.764	0.482	0.000	0.482	0.000
11+95.86	12+10.63	14.764	0.181	0.000	0.181	0.000
12+10.63	12+25.39	14.764	0.156	0.000	0.156	0.000
12+25.39	12+40.16	14.764	0.113	0.000	0.113	0.000
12+40.16	12+54.92	14.764	0.825	0.000	0.825	0.000
12+54.92	12+69.68	14.764	6.146	0.000	6.146	0.000
12+69.68	12+84.45	14.764	3.127	0.000	3.127	0.000
12+84.45	12+99.21	14.764	2.240	0.000	2.240	0.000
12+99.21	13+13.97	14.764	1.100	0.000	1.100	0.000
13+13.97	13+28.74	14.764	1.121	0.000	1.121	0.000
13+28.74	13+43.50	14.764	0.846	0.000	0.846	0.000
13+43.50	13+58.27	14.764	0.548	0.000	0.548	0.000
13+58.27	13+73.03	14.764	0.368	0.000	0.368	0.000
13+73.03	13+87.79	14.764	0.160	0.000	0.160	0.000
13+87.79	14+02.56	14.764	0.039	0.000	0.039	0.000
14+02.56	14+17.32	14.764	0.042	0.000	0.042	0.000

